









WASTE PIPE SIZES	
APPLIANCE	SIZE
WASH HAND BASIN	32ø (MAX LENGTH 1.7m & 0 BENDS)
WASH HAND BASIN	40ø (MAX LENGTH 3.0m & 2 BENDS)
SHOWER	40ø
KITCHEN SINK	40ø
DISHWASHER	40ø (MAX LENGTH 3.0m)
WC	110ø
2No. KITCHEN SINKS	50ø
1No. WASH HAND BASIN & KITCHEN SINK	40ø
FOR WASTE PIPE GRADIENTS REFER TO BS EN 12056 PART 2 : TABLE 6	



- NOTES:
1. THIS DRAWING IS THE COPYRIGHT© OF KEY IS. IT MUST NOT BE REPRODUCED OR USED FOR ANY PURPOSE WITHOUT PRIOR CONSENT.
 2. DO NOT SCALE FROM THIS DRAWING. WORK TO FIGURED DIMENSIONS ONLY. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.
 3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER MECHANICAL, ELECTRICAL & PUBLIC HEALTH DRAWING, SPECIFICATIONS AND SCHEDULES.

- | LEGEND | |
|--------|---|
| IV | ISOLATION VALVE |
| TBV | THERMOSTATIC BALANCING VALVE |
| NCV | NORMALLY CLOSED VALVE |
| SC | STOP COCK |
| LSV | LOCK SHIELD VALVE |
| | ¼ TURN VALVE |
| DOC | DRAIN VALVE |
| DRV | DOUBLE REGULATING VALVE |
| PRV | PRESSURE REDUCING VALVE |
| NRV | NON RETURN VALVE |
| TMV | THERMOSTATIC MIXING VALVE |
| | SOLENOID VALVE |
| | 3-PORT MOTORISED VALVE |
| CV | CHECK VALVE |
| DCV | DOUBLE CHECK VALVE |
| | TEMPERATURE/PRESSURE RELIEF |
| | COMMISSIONING SET |
| STR | "Y" TYPE STRAINER |
| AV | AUTOMATIC AIR VALVE |
| | AUTO BY-PASS VALVE |
| | PIPEWORK ANCHOR |
| | AXIAL EXPANSION JOINT |
| | PUMP FLEXIBLE CONNECTION |
| | UNION FITTING |
| TG | TEMPERATURE GAUGE |
| PG | PRESSURE GAUGE |
| | SINGLE PUMP (WITH FLANGES) |
| | TWIN (RUN/STANDBY) PUMP WITH AUTOMATIC AIR VENT |
| DPS | DIFFERENTIAL PRESSURE SWITCH |
| TS | TEMPERATURE SENSOR |
| PS | PRESSURE SENSOR |
| FS | FLOW SWITCH |
| TS | ZONE TEMPERATURE SENSOR (BMS) |
| | TEST POINT |
| | REDUCER |

GENERAL NOTES

1. DO NOT SCALE FROM THIS DRAWING.
2. POSITIONS OF ALL FITTINGS ARE INDICATIVE ONLY.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE RELEVANT SPECIFICATIONS.

ABOVE GROUND DRAINAGE NOTES

4. ALL FIRE STOPPING BY OTHERS, AS PART OF MAIN CONTRACTORS ELEMENT OF WORKS
5. FAIRFIRE PLUMBING SHALL BE PROVIDED WITH ANTI-VACUUM TYPE DEEP SEAL BOTTLE TRAPS
WHERE AIR ADMITTANCE VALVES ARE IDENTIFIED THEY SHALL BE INSTALLED
6. EACH ABOVE GROUND DRAINAGE SHALL COMPLY WITH THE REQUIREMENTS OF BS EN 12056 AND BUILDING REGULATIONS APPROVED DOCUMENT PART H.
7. ALL DRAINAGE PIPEWORK SHALL BE TESTED IN ACCORDANCE WITH BS EN 1610
8. ALL ABOVE GROUND (EXPOSED) DRAINAGE PIPEWORK SHALL BE IDENTIFIED USING COLOUR CODING TO BS 1710:2014.
9. ALL DRAINAGE PIPEWORK MUST HAVE A HIGH SOUND SENSITIVE AREAS SHALL BE ACoustICALLY SEALED AND INSULATED TO ENSURE THE ROOM ACOUSTIC PERFORMANCE IS NOT COMPROMISED.
10. ALL ABOVE GROUND DRAINAGE PIPEWORK SHALL BE LAID AT A MINIMUM FALL OF 1:80 UNLESS OTHERWISE STATED.
11. REFER TO ARCHITECTS SANITARY DETAILS FOR APPLIANCE CONNECTIONS.
12. ALL WASTE PIPES SHALL BE CHANGES OF DIRECTION ON ALL NEW WASTE PIPE & SHALL BE FULLY ACCESSIBLE FOR MAINTENANCE PURPOSES.
13. ALL NEW SVP STACKS WHICH DISCHARGE AT ROOF OR PLANTROOM ROOF LEVEL SHALL TERMINATE TO AT LEAST ONE (ONE) BELOW NORMAL FLOOR BOARDING FINISH LEVEL WITH COWL/BALCONY/CHIMNEY TERMINAL, OR TO A DEDICATED PLENUM ONLY.
14. CONDENSATE FROM AIR CONDITIONING UNITS SHALL BE INSTALLED IN UPVC & CONNECT TO THE DRAINAGE SYSTEM VIA AN INLINE HEPTVO TYPE TRAP.
15. RAINWATER AND SOIL VENT PIPEWORK TO BE INSULATED WITHIN 3 METRES OF THE POINT OF CONNECTION TO THE DRAINAGE SYSTEM.
16. CONDENSATION FORMATION UNLESS THE PIPEWORK IS WITHIN A SERVICES RISER.

WATER SERVICES NOTES

4. ALL FIRE STOPPING BY OTHERS, AS PART OF MAIN CONTRACTORS ELEMENT OF WORKS.
5. ALL CONCEALED HWYS PIPEWORK SHALL BE INSULATED IN ACCORDANCE WITH THE PROJECT SPECIFICATION.
6. ALL BOWS/MCWS PIPEWORK SHALL BE INSULATED AND VAPOUR SEALED IN ACCORDANCE WITH THE PROJECT SPECIFICATION.
7. ALL BOWS/MCWS PIPEWORK SHALL BE INSULATED WITH 25MM VALVES AND CHROME FINISH SHALL BE LEFT READY FOR DECORATIVE PAINTING BY OTHERS.
8. ALL INDIVIDUAL BRANCH PIPES TO ITEMS OF SANITARY WARE SHALL BE INSULATED WITH BALL VALVES.
9. ALL PIPEWORK DROPS TO BE CONTAINED IN IPS PANELS/STUD PARTITIONING TO BE INSULATED.
10. AIR TESTS TO BE FITTED AT ALL HIGH POINTS IN SYSTEM PIPEWORK.
11. DRAIN COCKS SHALL BE FITTED AT LOW POINTS IN SYSTEM PIPEWORK.
12. ALL SERVICES DROPPING TO LOW LEVEL TO BE IN WALL/IPS IF POSSIBLE. BOXING OF SERVICES DROPPING TO LOW LEVELS TO BE IN WALLS/IPS IF POSSIBLE.
13. ALLOW ALL DROPS, BRANCHES & DIRECTION CHANGES TO BE FREE TO FLEX.